

Summary of safety training and safety instructions for working on a construction site



**Goggles are
a must**



**Wearing a
protective
helmet is
mandatory**



**Protective
footwear is
mandatory**

Personal Protective Equipment

Negative impact	Failure/Negative Scenario	Risk Elimination/Minimization/Prevention
- Physiological injuries - Limb and eye injuries - Health damage	- Failure to use personal protective equipment - Failure to inspect personal protective equipment - Improper use of personal protective equipment	- Each employee will be equipped with standard work shoes, a protective helmet and a reflective vest - In addition, the employee will use additional personal protective equipment according to the type of work and in accordance with the Personal Protective Equipment Law, manufacturer's instructions. For any inquiries regarding this matter, contact the Ministry of Defense - If the equipment is not in good condition, replace it immediately - My signature on this document constitutes a commitment to use personal protective equipment and to act according to the briefing I received



Caution
**Tractor in
motion**

Engineering Mechanical Equipment

Negative impact	Failure/Negative Scenario	Risk Elimination/Minimization/Prevention
- Run-over - Bodily injury - Sliding - The broken pieces	- Operation by unauthorized / inexperienced personnel - Injury to workers during work transition - Workers falling from engineering equipment - Overturning of engineering mechanical equipment	Operation of engineering mechanical equipment only by licensed and experienced personnel Engineering mechanical equipment will have a reverse horn, headlights, luminous stripes and a checker When moving or working, be alert and maintain a safety distance, approach engineering mechanical equipment with eye contact with the operator Beware of engineering mechanical equipment that is traveling in reverse, traveling in reverse with an escort Maximum speed 10 km/h, boarding / disembarking from the vehicle from the designated places



Summary of safety training and safety instructions for working on a construction site



**Damaged ladder
Use prohibited**



**Beware of
falling**

Working at Height

Negative impact	Failure/Negative Scenario	Risk Elimination/Minimization/Prevention
· Falling from high levels and scaffolding · Falling from work at height equipment such as platforms and ladders · Electric shock at height	· An employee who is not qualified or skilled to perform work at height · Incorrect/incorrect/inappropriate work equipment · No standard and safe guardrail to prevent falls · Failure at anchor point	· Definition: Working at height with a risk of falling to a depth of 2 m · No standard guardrail, tilting the human body beyond the guardrail, from work equipment height of the lifting basket · Mechanized scaffolding lifting basket · Personal protective equipment and aids for working at height: will be checked before use, work according to work at height regulations and manufacturer's instructions. Report any defect or defect · Ladders: climbing up to a meter from the top edge, walking prohibited, not for prolonged work · Scaffolding platforms and baskets: work with the permission of the foreman · Scaffolding/work surfaces: do not disassemble parts, at least 60 cm wide, climbing/descending from ladders, do not place a ladder on the scaffold · General: work in suitable weather and lighting conditions for work and operation of equipment, anchor point 1.5 tons, work at a height of at least two people, mandatory use of a helmet with santeria, full body harness, fall prevention/bracing security system



Electricity and moving electrical equipment



Danger



**Protection is
a must**

Negative impact	Failure/Negative Scenario	Risk Elimination/Minimization/Prevention
- Electric Shock - Burns\Eye Injuries\Arc Flash Fire	- Use of faulty or incorrect electrical equipment - Repairs by unauthorized persons - Damage to cables and electrical infrastructure - Electrical shock from live electricity - Extension cord in a wet environment	- Electrical equipment: Use according to its intended purpose and according to manufacturer's instructions, will be inspected by a certified electrician and before use, if not working properly, work must be stopped and the foreman must be notified, do not dismantle shields and guards, repairs by authorized persons, do not operate in a wet environment, the employee must be knowledgeable in operating the equipment - Cables: double insulation, not on the floor or in a wet environment, industrial socket/plug, feed through a conduit, connect after deployment, disconnect before folding - Electrical work: not with live voltage, under the supervision of a licensed electrician, lock the power sources and switch them off, do not perform in a wet environment and without sufficient lighting and in dangerous weather, maintain a distance of at least 5 m from an overhead network



Danger! Do not stand under a raised load

Lifting work

Negative impact	Failure/Negative Scenario	Risk Elimination/Minimization/Prevention
- Body Injuries - Limb Injuries - Crushed - Head Injuries	- Lifting Equipment/Accessories Failure - Worker Injuries from Lifted Loads - Falling Load Parts	Lifting equipment and lifting accessories: Will be inspected by a qualified inspector and before use, will be operated by licensed and experienced operators Lifting work: With the approval of the foreman, fencing the lifting area, tying and guiding with shovels, do not work under a lifted load, handling a load one meter above the floor To prevent parts from falling: Lifting with designated tools, tying and clamping loads, working carefully and vertically

Summary of safety training and safety instructions for working on a construction site



!Danger

Open Channel

Excavations

Negative impact	Failure/Negative Scenario	Risk Elimination/Minimization/Prevention
- Injuries - Falls - Excavation collapse - Electrical shock - Strikes	- Workers Falling in Excavation - Excavation Collapse - Infrastructure Damage - Construction Equipment Overturning - Crawler Strikes	- Excavation shall be carried out with the approval of the foreman and after scanning infrastructure and animals - Working near infrastructure with hand tools and with caution - Ascending and descending from designated locations, excavation fencing and signage required - Excavation according to natural slope/backfilling, taking measures to prevent collapse - Excavation width shall allow for work to be carried out, passages above excavation 60 cm - Engineering equipment shall approach to a safe distance, workers shall not work in the vicinity of the equipment



Fire, open flame and smoking are prohibited

Hot jobs

Negative impact	Failure/Negative Scenario	Risk Elimination/Minimization/Prevention
- Eye injuries - Burns - Fire/fire - Explosions - Electric shock	- Improper use of personal protective equipment, equipment failure - Gas cylinder explosion - Employee/equipment/environmental fires	- Hot work: After approval from the foreman, infrastructure protection, appropriate personal protective equipment, fire watch in the area during and after execution, keep flammable/combustible materials at least 10 m away, have appropriate fire extinguishing equipment, keep electrical cables away - Gas cylinders: Handling by knowledgeable workers, safe transportation, fix perpendicular to the floor, use covers, keep oils away, keep away from heat sources, proper piping with standard, proper and valid safety equipment

Summary of safety training and safety instructions for working on a construction site



!Danger

Hazardous Materials

Hazardous Materials

Negative impact	Failure/Negative Scenario	Risk Elimination/Minimization/Prevention
- Choking/Dizziness - Burns - Fires/Explosions - Occupational Diseases	- Use of substances harmful to health - Personal protective equipment not appropriate for the hazard/improper - Working in an unventilated area	- Use chemical materials after receiving a safety briefing in accordance with the material's safety data sheet - Work with personal protective equipment in accordance with the material's safety data sheet - Ventilate the workplace and keep fire away from flammable materials - Destroy empty packaging/containers after use and do not leave in the field



General Safety Guidelines

Proper lifting prevents a lot of suffering

Do	Don't
- Enter the site through the designated entrances and beware of engineering equipment - Behave according to the warning signs on the site - Lifting equipment and materials close to the body and not more than 25kg - Start lifting by bending your knees, use an additional worker - Cover openings and pits to prevent workers from falling - Report any defect, danger, hazard/dangerous incident/accident to the Safety and Health Department - Consult the Safety and Health Department Safety Supervisor on any work that is unclear to you - Remain on site as long as a foreman is on site - Do not perform work above or below other workers - If first aid is needed, contact the foreman - Ensure sufficient lighting to perform the work safely	- Do not use the phone while walking or performing a task - Do not repair/operate equipment that you are not familiar with - Do not intentionally perform an action that could cause harm to you or others - Do not use equipment that is not working properly or is not suitable for the task - Do not dismantle a railing/fencing without permission from the foreman - Do not throw material/equipment. It must be lowered in a controlled manner - Do not jump/climb over a scaffold or ladder - Do not load more than the permitted weight - Do not work in a place where there is a risk of falling and there is no means of preventing falling - Do not perform work if it is not clear to you from a professional and safety perspective - Do not perform work alone